



NOTES:

1. DOOR IS NOT SHOWN. FOR INFORMATION SEE DETAIL ED.231.
2. FOR CABLING SCHEMATIC SEE DETAIL NO. ED.212.
3. INSTALL GROUND WIRE BETWEEN EQUIPMENT GROUNDING BAR AND DOOR GROUNDING LUG. INSTALL GROUND LUG ON PROVIDED ENCLOSURE DOOR TAB.
4. VERIFY THE OPENING AND CLOSING OF THE ENCLOSURE DOES NOT INTERFERE WITH MILLWORK, LIGHT FIXTURES, CEILING GRID, ETC.
5. CPS TO PROVIDED CISCO SWITCH. (1-2) 24 PORT OR (1) 28 PORT SWITCH(ES). ENCLOSURE MAXIMUM CAPACITY IS 48 PORTS.
6. 1-FEET BLUE PATCH CORDS TO BE USED FOR DATA PORT CONNECTIONS. 1-FEET PURPLE PATCH CORDS TO BE USED FOR DVS CAMERA CONNECTIONS.

KEYED NOTES

- 1 WALL MOUNTED EQUIPMENT CABINET (CONCENTRATOR ENCLOSURE).
- 2 FIBER OPTIC PATCH PANEL WITH 6 LC CONNECTORS AND SIDE RAILS FOR PULL-OUT ACCESS.
- 3 WIRE MANAGER PANEL
- 4 CATEGORY 6 UTP 48-PORT PATCH PANEL (ORANGE).
- 5 QUADRUPLEX ISOLATED GROUND (IG) RECEPTACLE (ORANGE) MOUNTED IN REAR OF CABINET IN LEFT HAND CORNER, CONDUIT SHALL BE PLACED IN CORNER OF CONCENTRATOR BEHIND MOUNTING RAIL SO AS NOT TO INTERFERE WITH EQUIPMENT. PROVIDE ONE IG 20A, 120V, 1-PHASE, DEDICATED, ISOLATED GROUND CIRCUIT.
- 6 24-PORT OR 48-PORT CISCO NETWORK SWITCH. SEE NOTE 5.
- 7 COPPER EQUIPMENT GROUND BAR, PROVIDED IN ENCLOSURE.
- 8 ENCLOSURE DOOR GROUNDING LUG, ONE ON EACH VERTICAL SIDE ADDED TO DOOR. SEE NOTE 3.
- 9 19" WIDE EQUIPMENT RACKS.
- 10 VENTILATION LOUVERS TO BE PROVIDED ON BOTH SIDE PANELS (LOUVERS ARE NOT SHOWN) WITH LOUVERS OPENINGS FACING DOWNWARD.
- 11 48 PORT CAT 5E PATCH PANEL. PORTS 1-24 FOR 25 PAIR CAT 5E. PORTS 25-48 FOR INDIVIDUAL STATION CABLES. TERMINATE PAIR 1 ONLY.
- 12 CATEGORY 6 UTP 48 PORT PATCH PANEL (BLUE).

CHICAGO PUBLIC SCHOOLS CAPITAL IMPROVEMENT PROGRAM INFORMATION TECHNOLOGY SERVICES INFRASTRUCTURE STANDARDS ADMINISTRATIVE CONCENTRATOR ENCLOSURE (ACE) CABLING SCHEMATIC			
	PROJECT NUMBER	SCALE NONE	DATE 02/14/19
	APPROVED		SHEET NO. ED.202

NO.	DATE	REVISION	BY