



KEYED NOTES

- ① PAIRS 1 THRU 25 DEDICATED FOR INTERCOM ADM TERMINATIONS.
- ② CROSS-CONNECT TERMINATION PROVIDED BY CPS.
- ③ TERMINATE 4-PR CAT 5E UTP CABLES IN INTERCOM CONTROL CABINET (ICC) ON PUNCH DOWN BLOCK PROVIDED WITH SYSTEM. ICC IS TYPICALLY LOCATED IN WORKROOM.
- ④ CROSS CONNECTION TO PBX PROVIDED BY C.P.S.

CHICAGO PUBLIC SCHOOLS CAPITAL IMPROVEMENT PROGRAM INFORMATION TECHNOLOGY SERVICES INFRASTRUCTURE STANDARDS			
INTERCOM/PAGING PBX CONNECTIVITY SCHEMATIC			
			SHEET NO.
			ED.811
	PROJECT NUMBER	SCALE NONE	DATE 08/28/08
	NO. DATE	REVISION	BY

	PROJECT NUMBER	SCALE NONE	DATE 08/28/08
	NO. DATE	REVISION	BY